

CCHS – Substructure Cont'd Story Board



Under slab drainage needs to be installed before the modular buildings can be positioned. These drainage runs will discharge the foul water from the building when in occupation.



The foul drainage is installed using plastic pipe and connectors. These pipe runs are bedded on granular material to the designed falls. Each individual run will discharge into an 'inspection chamber' or 'manhole'.



The sports hall floor construction is a block & beam system that sits on sleeper walls. These sleeper walls are built out of brick and blockwork.